

15

10


2+50


lг				Ш
7				
- D				
-				
-				
11.550	NO.	REVISIONS	ВУ	D/


H RIVER PLANTATION WWTP PHASE I
STORM DRAIN PROFILES


KIAWAH RIVER PLANTATION HOLDINGS, LP KIAWAH


JOB NO: J-25328.0002
DATE: I2/I6/I6
DRAWN: DNF
DESIGNED: MFY
REVIEWED: MFY
APPROVED: MFY
SCALE: AS SHOWN















STRIPPIN N	ENGINA	WWWWWWWWWW
TH CARO	No. 13293	Manual A A A Manual A A A A A A A A A A A A A A A A A A A
THINNING.	mmmm Garene	MANUFACTURE OF THE PARTY OF THE
		11.0


PHASE


DETAILS AND SECTIONS

JOB NO: J-25328.0002
DATE: I2/I6/I6
DRAWN: DNF
DESIGNED: KEN
REVIEWED: MFY
APPROVED: MFY
SCALE: AS NOTED

(IN FEET) 1 inch = 3 ft.









THOMAS Engineering | Surveying


STORAGE LAGOON WTP PHASE ANTATION EFFLUENT SECTIONS Ы


KIAWAH RIVER F DETAILS AND SECTION


DATE: 12/16/16
DRAWN: DNF
DESIGNED: KEN REVIEWED: MFY APPROVED: MFY













KIAWAH RIVER FEFFLUENT PUMP 3 DATE: DRAWN: 12/16/16 DESIGNED: KEN REVIEWED: MFY APPROVED: MFY


SECTION WWTP PHASE I

PLANTATION V


WAH RIVER PLANTATION
HOLDINGS, LP








WARNING SIGN DETAIL



VALVE BOX DETAIL
SCALE: NONE



NOTES:


- I. NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THE MINIMUM STONE AND SAND BEDDING AS SHOWN ON THE DETAILS. PAYMENT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR INSTALLING THE PIPING ASSOCIATED WITH THE BEDDING.
- 2. WHERE THE ENGINEER DETERMINES ADDITIONAL UNDERCUTTING AND STONE BACKFILL IS REQUIRED TO PROVIDE A STABLE SUBGRADE, IT SHALL BE PAID FOR AT THE COST OF REMOVING THE ADDITIONAL UNSUITABLE MATERIAL, BEYOND THAT SHOWN ON THE DETAILS, AND FURNISHING AND
- INSTALLING ADDITIONAL STONE BACKFILL.

 3. BECAUSE THE AMOUNT OF ADDITIONAL UNDERCUTTING STONE BEDDING REQUIRED IN AREAS OF WEAK AND UNSTABLE SUBGRADEIS UNKNOWN, THE BID FORM INCLUDES 200 CUBIC YARDS (CY) OF STONE BEDDING, AND 200 CUBIC YARDS OF SAND BACKFILL IN ORDER TO ESTABLISH A UNIT PRICE FOR THESE ITEMS. NO PAYMENT FOR ADDITIONAL STONE OR SAND BACKFILL BEYOND THE QUANTITY SHOWN ON THE DETAILS SHALL BE PAID WITHOUT PRIOR WRITTEN APPROVAL OF LOCATION.
- SHOWN ON THE DETAILS SHALL BE PAID WITHOUT PRIOR WRITTEN APPROVAL OF LOCATION, QUANTITY, AND OVERALL PRICE BY ENGINEER.

 4. NO SEPARATE MEASUREMENT OR PAYMENT WILL BE MADE FOR THE EXCAVATION, REMOVAL, AND DISPOSAL OF MATERIAL DEEMED UNSUITABLE FOR GENERAL BACKFILL, AND SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR INSTALLING THE PIPING ASSOCIATED WITH THE BACKFILL OPERATION.

PIPE BEDDING DETAILS

LE: NONE





GKEL# ZO 10-10Z-2 - Fage 10 OLIZ

Engineering | Surveying | Planning | GIS | Consulting

VER PLANTATION
DINGS, LP
COUNTY, SOUTH CAROLINA
ANTATION WWTP PHASE I


HOLDINGS,

CHARLESTON COUNTY, SOU

KIAWAH RIVER PLANTATIC

JOB NO: J-25328.0002
DATE: I2/I6/I6
DRAWN: DNF
DESIGNED: KEN
REVIEWED: MFY
APPROVED: MFY

09-C-02



STRUCTURE NOTES:

1.00 PRECAST CONCRETE

- I.OI PRECAST CONCRETE DESIGN, MANUFACTURE AND ERECTION SHALL CONFORM TO THE FOLLOWING: A. ACI 318 "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", LATEST EDITION.
 - B. PCI MNL-117 "MANUAL FOR QUALITY CONTROL FOR PLANTS AND PRODUCTION OF PRECAST CONCRETE PRODUCTS", LATEST EDITION.
- C. PCI DESIGN HANDBOOK, LATEST EDITION. 1.02 PRE-CAST CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 4,000 PSI.
- 1.03 REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60 UNLESS NOTED OTHERWISE. 1.04 PRECAST MANUFACTURER IS RESPONSIBLE FOR THE STRUCTURAL DESIGN OF PRECAST ELEMENTS AND THEIR CONNECTIONS. DESIGN SHALL BE PERFORMED BY A STRUCTURAL ENGINEER REGISTERED IN THE PROJECT STATE. SHOP DRAWINGS AND CALCULATIONS SEALED BY THE ENGINEER SHALL BE SUBMITTED. REVIEW OF CALCULATIONS AND SHOP DRAWINGS SHALL BE FOR GENERAL CONFORMANCE
- WITH THE CONTRACT DOCUMENTS AND SHALL NOT RELIEVE CONTRACTOR AND ITS ENGINEER OF THE FULL RESPONSIBILITY FOR DESIGN OF PRECAST AND CONNECTIONS. DO NOT BEGIN FABRICATION UNTIL SHOP DRAWINGS ARE COMPLETED AND REVIEWED.
- 1.05 DESIGN OF PRECAST MEMBERS AND CONNECTIONS SHALL INCLUDE BUT NOT LIMITED TO THE FOLLOWING: DEAD LOAD - ACTUAL WEIGHT OF STRUCTURE + EQUIPMENT
 - LIVE LOAD = 300 PSF MIN.
 - WIND LOAD NOT APPLICABLE LATERAL EARTH PRESSURE = 200 PSF MIN.
 - SIESMIC LOADS = 0.086 * W (DETERMINE "W" IN ACCORDANCE WITH ASCE 7-10)
- 1.06 UNLESS NOTED OTHERWISE ALL EXPOSED STEEL ANCHORS AND PLATES SHALL BE 316 STAINLESS STEEL. 1.07 REPRODUCED COPIES OF ASTM C1433 "STANDARD SPECIFICATION FOR PRECAST REINFORCED CONCRETE MONOLITHIC BOX SECTIONS FOR CULVERTS, STORM DRAINS AND SEWERS" WILL NOT BE ACCEPTED
- 1.08 DURING HANDLING, STORAGE, AND TRANSPORTING, LIFT AND SUPPORT MEMBERS ONLY AT THE LIFTING AND SUPPORT POINTS SHOWN ON THE SHOP DRAWINGS. USE PROPER EQUIPMENT AND METHODS OF BRACING DURING TRANSPORTATION TO INSURE MEMBERS WILL ARRIVE AT THE JOB SITE UNDAMAGED. PROVIDE PADDING TO PREVENT CHIPPING OF THE CONCRETE.
- 1.09 IF CAST-IN LIFTING LOOPS OR INSERTS ARE USED, CUT OFF LOOPS OR INSERTS A MINIMUM OF 1/2" BELOW SURFACE AND FILL RECESS WITH AN EPOXY GROUT ACCEPTED BY THE ENGINEER.

2.00 STRUCTURAL FILL AND COMPACTION

- 2.01 THE SOILS TO BE USED AS STRUCTURAL FILL SHALL BE FREE OF ORGANICS, ROOTS, OR OTHER DELETERIOUS MATERIALS. IT SHALL BE NON-PLASTIC GRANULAR MATERIAL CONTAINING LESS THAN 25
- PERCENT FINES PASSING THE NO. 200 SIEVE. 2.02 ALL STRUCTURAL FILLS SHALL BE PLACED IN THIN (EIGHT TO TEN INCHES LOOSE) LIFTS AND COMPACTED TO A MINIMUM OF 95% OF THE SOIL'S MODIFIED PROCTOR MAXIMUM DRY DENSITY (ASTM
- 2.03 FILL BROUGHT TO THE SITE SHALL BE WITHIN THREE PERCENT (WET OR DRY) OF THE OPTIMUM MOISTURE CONTENT. SOME MANIPULATION OF THE MOISTURE CONTENT (SUCH AS WETTING, DRYING) WILL BE REQUIRED DURING THE FILLING OPERATION TO OBTAIN THE REQUIRED DEGREE OF COMPACTION.
- 2.04 CONTRACTOR SHALL PROVIDE COMPACTION TEST RESULTS FOR ALL FILL MATERIAL WITHIN AREA OF THE STRUCTURE. A MINIMUM OF ONE (I) TEST SHALL BE PERFORMED AND RESULTS SUBMITTED TO ENGINEER PRIOR TO ACCEPTANCE OF THE STRUCTURE.

PHASE 1A LAS DESIGN

Zone	Area (ac)	Model No.	Flow/head (gpm)	Diam. (ft)	Press. (psi)	Spacing (ft)	Equivalent # Heads	Actual # Heads	Frequency (min)	Capacity (gpd)	Cumulative (gpd)
1.01	3.33	5023-2, 18x8	19.3	115	60	60	19.0	19.0	70.38	25,807.50	25,807.50
1.02	3.26	5023-2, 17x8	15.3	110	45	50	23.0	23.0	71.80	25,265.00	51,072.50
1.03	3.42	5023-2, 17x8	15.3	110	45	52	24.5	25.0	70.71	26,505.00	77,577.50
1.04	3.44	5023-2, 18x8	19.3	115	60	65	19.5	20.0	70.84	26,660.00	104,237.50
1.05	3.20	5023-2, 17x8	15.3	110	45	52	23.0	23.0	70.47	24,800.00	129,037.50
TOTAL	16.65									129,037.50	

I. ALUMINUM ACCESS HATCH SHALL BE EQUIVALENT TO

HALLIDAY PRODUCTS MODEL WIS3648 CHANNEL FRAME

COVER w/ 300 P.S.F. MINIMUM LOAD RATING.

PAINTED SAFETY ORANGE.

OVERALL

1 1/2" (38 MM) 1/4" (7 MM) THICK DIAMOND ALUMINUM COUPLING PATTERN ALUM. COVER PLATE

BITUMINOUS

SECTION

ACCESS DOOR

DETAIL

SCALE: NONE

COATING

3 3/4"

(95 MM) TYP.

2. THE ALUMINUM ACCESS HATCH SHALL INCLUDE

STEEL SAFETY GRATING. STEEL GRATING SHALL

STANDARDS 1910.23 AND 1910.146. GRATING SHALL BE

S.STL. & ALUM. POSITIVE LOCKING HOLD OPEN ARM WITH S.ST. SPRING

T-316 STAINLESS STEEL

(COVER SHOWN IN OPEN


F FASTENERS


DETAIL

HINGES WITH TAMPER PROO

CONFORM TO THE LATEST REVISIONS OF OSHA


- Model number refers to sprinkler head manufactured by Sennniger-Impact 50 Series or approved equal.
- "Frequency" is the allowable run time per zone per day which provides a minimum spray: rest ratio of 1:20
- "Capacity" of each zone is calculated based upon 2"/acre/week (7,750 gpd/acre) with all heads running allowable run time
- Diameter of spray head coverage area is based upon a 1.5 foot mounting height above ground surface
- Provide purple or lavender caps to denote non-potable or treated effluent water.





SPRAY RISER DETAIL w/ DRAIN





DRAWN:

DESIGNED: KEN

REVIEWED: MFY

APPROVED: MFY

SCALE: AS NOTED



2404 Rutland Dr., Suite 200 Austin, Texas 78758 phone: (512) 834-6000 | fax: (512) 834-6039

microBLOX ™

Sheet Index

- I-1.1 CODES LEGEND I-1.2 SYMBOLS LEGEND

- TRANSFER AND WAS PUMPS
- PERMEATE CONTROL AND DISINFECTION
- **BLOWERS**
- I-1.8 SUPPLEMENTAL OXYGEN

INITIAL RELEASE ©COPYRIGHT 2010 OVIVO **REVISION** ALL RIGHTS RESERVED - REV A

THIS DRAWING CONTAINS CONFIDENTIAL PROPRIETARY INFORMATION OF OVIVO, AND ITS AFFILIATES, AND IS NOT TO BE DISCLOSED NOR TO BE USED EXCEPT FOR EVALUATING PROPOSALS OF OVIVO OR INSTALLING, OPERATING OR MAINTAINING OVIVO EQUIPMENT, UNLESS OTHERWISE AUTHORIZED IN WRITING BY OVIVO. UNCONTROLLED COPY IF PRINTED

DO NOT SCALE PRINTS

WORKMANSHIP STANDARD ES0001 APPLIES

microBLOX ™

P&ID

COVER SHEET

DATE 6/22/16 BY MCS CHECK'D PDF DWG SCALE JOB NUMBER 061016-1-DS-R1 I-1.0 OF 9

DATE: 12/16, DRAWN: DNF DESIGNED: MFY REVIEWED: MFY

PHASE